



REMOVE PAPER SEALS BEFORE INSTALLATION

INSTALL VERTICALLY ONLY (K2 MARK AT TOP)

TIGHTEN FLANGE BOLTS BEFORE USE

NIP-UP LARGE NUT AROUND SHAFT

FIT HANDLE TO SHAFT IN REQUIRED POSITION

USE FOOT VALVE ON SUCTION LIFT  
GREATER THAN 2M

K2 PERFORMANCE

APPROX 3.5m LIFT, 3.0m DELIVERY & 1" PIPE

**26 lpm - SINGLE STROKE •**

**37 lpm - DOUBLE STROKE •**

all approx figures